



11986 NW 97th Avenue, Hialeah Gardens, FL 33018

Tel: (305) 556-0473 • Fax: (305) 556-8268

CARIBBEAN BLVD. FROM C-1N CANAL TO CORAL SEA ROAD
JOINT PARTICIPATION AGREEMENT
TOWN OF CUTLER BAY, FL
MIAMI-DADE COUNTY PROJECT No. 20140153

BID FORM
PREPARED 05/26/2015

ITEM	DESCRIPTION	TOTAL		UNIT	
		QUANTITY	UNIT	PRICE	AMOUNT
101-1	Mobilization	L.S.	1	\$ 70,847.06	\$ 70,847.06
102-1	Maintenance of Traffic and Access	L.S.	1	\$ 61,056.00	\$ 61,056.00
104-1	Prevention, Control & Abatement of Erosion and Water Pollution	L.S.	1	\$ 6,112.94	\$ 6,112.94
110-1-1-1	Clearing & Grubbing	L.S.	1	\$ 71,027.07	\$ 71,027.07
110-7-1	Mail Box Relocation	EA	1	\$ 564.71	\$ 564.71
110-8	Back of sidewalk restoration (inc. sod, landscaping, asphalt/paver/concrete driveways, edge concrete curbing, irrigation and electrical systems as needed)	L.S.	1	\$ 15,489.40	\$ 15,489.40
120.1	Regular Excavation	C.Y.	3,659	\$ 1.39	\$ 5,086.01
120-6	Embankment	C.Y.	1,245	\$ 4.87	\$ 6,063.15
160-4	Type B Stabilized Sub- Base (12" thick, LBR=40)	S.Y.	11,452	\$ 1.51	\$ 17,292.52
210-1-1	Limerock Base (8" thick) Single course Primed	S.Y.	11,145	\$ 8.39	\$ 93,506.55
334-2-13	Type SP Structural Course (2"thick)	TN	1,226	\$ 109.16	\$ 133,830.16
334-2-23	Type FC-9.5 Friction Couese (1" Thick)	TN	613	\$ 122.22	\$ 74,920.86
327-70-1	Milling (1") Asphalt	SY	458	\$ 4.50	\$ 2,061.00
425-1-321	Curb Inlet Type P-2 (< 10')	EA	7	\$ 5,568.50	\$ 38,979.50
425-1-201	Curb Inlet Type P-9 (< 10')	EA	1	\$ 3,623.23	\$ 3,623.23
425-1-341	Curb Inlet Type P-4 (< 10')	EA	1	\$ 5,630.46	\$ 5,630.46
425-1-351	Curb Inlet Type P-5 (< 10')	EA	2	\$ 4,682.84	\$ 9,365.68
425-1-361	Curb Inlet Type P-6 (< 10')	EA	11	\$ 4,816.66	\$ 52,983.26
425-2-42	Manhole Type P-7T (any dimension, maximun depth 15')	EA	5	\$ 5,685.28	\$ 28,426.40
425-2-42	Manhole Type "J"	EA	9	\$ 7,063.31	\$ 63,569.79
425-6	Adjust existing valve boxes, meter Boxes, FH and Manhole covers	LS	1	\$ 9,924.27	\$ 9,924.27
430-173-115	CAP Pipe Culvert -15 " Diam	L.F.	717	\$ 40.33	\$ 28,916.61
430-173-124	CAP Pipe Culvert -24" Diam	L.F.	247	\$ 48.66	\$ 12,019.02
443-70-6	Exfiltration Trench (36" Diameter)	L.F.	2,200	\$ 130.02	\$ 286,044.00
520-1-10	Conc. Curb and Gutter "F"	L.F.	4,778	\$ 14.42	\$ 68,898.76
520-2-8	Conc. Curb Valley	L.F.	318	\$ 16.11	\$ 5,122.98
520-2-4	Conc. Curb "D"	L.F.	340	\$ 13.89	\$ 4,722.60

CARIBBEAN BLVD. FROM C-1N CANAL TO CORAL SEA ROAD
JOINT PARTICIPATION AGREEMENT
TOWN OF CUTLER BAY, FL
MIAMI-DADE COUNTY PROJECT No. 20140153

BID FORM
PREPARED 05/26/2015

ITEM	DESCRIPTION	TOTAL	UNIT		
		QUANTITY	UNIT	PRICE	AMOUNT
522-1	Conc. Sidewalk (4" thick)	S.Y.	1,351	\$ 28.53	\$ 38,544.03
522-2	Conc. Sidewalk (6" thick) Regular	S.Y.	1,624	\$ 34.64	\$ 56,255.36
522-3	Colored Concrete Crosswalks (12" thick)	S.F.	743	\$ 13.08	\$ 9,718.44
522-3-A	Colored Conc. Bus bay (12" thick)	S.F.	2,051	\$ 13.08	\$ 26,827.08
527-1-A	Detectable Warning Surface	S.F.	90	\$ 20.00	\$ 1,800.00
550-102-18	Relocate Existing Fence	LF	180	\$ 40.00	\$ 7,200.00
575-1-1	Sodding	S.Y.	6,599	\$ 2.50	\$ 16,497.50
580-2A	Landscaping	L.S.	1	\$ 165,078.82	\$ 165,078.82
630-1-12	Conduit 2" PVC, Underground	L.F.	50	\$ 11.67	\$ 583.50
630-1-13	Conduit 2" PVC, Under Pavement	L.F.	180	\$ 15.56	\$ 2,800.80
635-1-11	Pull Box	EA	9	\$ 638.89	\$ 5,750.01
660-2-101	Traffic signal Loop	EA	4	\$ 1,094.44	\$ 4,377.76
672-1-4	Modify Existing Controller	EA	1	\$ 1,400.00	\$ 1,400.00
700-11-500	Electronic Display sign, school solar powered relocate	EA	4	\$ 1,176.47	\$ 4,705.88
700-40-1	R1-1 W/ D3-1 sign Assembly	EA	2	\$ 227.78	\$ 455.56
700-40-1	R2-1 Sign Assembly	EA	4	\$ 200.00	\$ 800.00
700-40-1	R3-17 Sign Assembly	EA	5	\$ 200.00	\$ 1,000.00
700-40-1	R3-17(w/R3-17aP) Sign Assembly	EA	1	\$ 227.78	\$ 227.78
700-40-1	R3-17 (w/ R3-17bP) Sign Assembly	EA	1	\$ 227.78	\$ 227.78
700-40-1	S1-1 / W16-7PL sign Assembly	EA	4	\$ 233.33	\$ 933.32
700-40-1	Bus Stop Sign Assembly	EA	4	\$ 211.11	\$ 844.44
700-40-1	R4-11 Sign Assembly	EA	1	\$ 200.00	\$ 200.00
700-40-1	S1-1/ W16-P sign Assembly	EA	1	\$ 233.33	\$ 233.33
700-46-11	Remove Existing sign	EA	12	\$ 27.78	\$ 333.36
700-46-21	Relocate Existing sign	EA	1	\$ 55.56	\$ 55.56
706-3	Marker pavement Retro-Reflective	EA	210	\$ 3.17	\$ 665.70
711-11-160	Thermoplastic (white)(message)(SCHOOL)	EA	2	\$ 100.00	\$ 200.00
711-11-160	Thermoplastic (white)(message)(BUS, ONLY)	EA	6	\$ 94.44	\$ 566.64
711-11-160	Thermoplastic (white)(message)(BIKE LANE LOGO & ARROW)	EA	6	\$ 534.00	\$ 3,204.00
711-11-160	Share Lane Symbol Preformed Thermoplastic	EA	1	\$ 382.35	\$ 382.35
711-11-170	Thermoplastic (white)(arrows)	EA	12	\$ 50.00	\$ 600.00
711-11-241	Thermoplastic (yellow) (6") 10'-30' skip	L.F.	1,290	\$ 0.66	\$ 851.40
711-11-151	Thermoplastic (white) (6")2'-6' Skip	L.F.	280	\$ 0.66	\$ 184.80
711-11-121	Thermoplastic (white) (solid) (6")	L.F.	6,190	\$ 0.64	\$ 3,961.60
711-11-125	Thermoplastic (white) (solid) (24")	L.F.	618	\$ 2.94	\$ 1,816.92

CARIBBEAN BLVD. FROM C-1N CANAL TO CORAL SEA ROAD
JOINT PARTICIPATION AGREEMENT
TOWN OF CUTLER BAY, FL
MIAMI-DADE COUNTY PROJECT No. 20140153

BID FORM
PREPARED 05/26/2015

ITEM	DESCRIPTION	TOTAL		UNIT	
		QUANTITY	UNIT	PRICE	AMOUNT
711-11-221	Thermoplastic (yellow) (solid) (6")	L.F.	4,234	\$ 0.64	\$ 2,709.76
711-11-224	Thermoplastic (yellow) (solid) (18")	L.F.	191	\$ 1.78	\$ 339.98
	Green Colored Pavement	SF	1,500	\$ 3.24	\$ 4,860.00
620-1-1	Grounding Electrode	L.F.	29	\$ 5.56	\$ 161.24
715-1-113	Conductor, F&I, Insulated No. 6	L.F.	5,754	\$ 1.39	\$ 7,998.06
715-2-215	Conduit PVC Sch 40-2"	L.F.	5,231	\$ 11.46	\$ 59,947.26
715-7-11	Load Center, Complete	EA	1	\$ 7,222.22	\$ 7,222.22
715-14-11	Pull Box	EA	29	\$ 638.89	\$ 18,527.81
715-31	Maintenance of Existing lighting OR Temp lighting	L.S.	1	\$ 100.00	\$ 100.00
715-36-12	Frangible Base for Light Pole	EA	19	\$ 436.67	\$ 8,296.73
715-511-145	Lighting poleComplete including foundation, cable distribution, pole and luminaire	EA	19	\$ 10,041.11	\$ 190,781.09
	SUB - TOTAL				\$1,836,311.86
	MISCELLANEOUS ITEMS				
800-6	FPL Connection & MDWASD Meter Allowance	L.S.	1	\$ 27,777.77	\$ 27,777.77
800-7	Permit Allowance	L.S.	1	\$ 8,661.90	\$ 8,661.90
800-8	Off Duty Police Allowance	L.S.	1	\$ 27,108.97	\$ 27,108.97
980	Safety Act	L.S.	1	\$ 536.39	\$ 536.39
990	Advance Exploration of Existing Utilites	L.S.	1	\$ 21,176.47	\$ 21,176.47
991	Project Signs Double Sided 4'x8' with Color Graphic, as Directed by Town	EA	2	\$ 778.78	\$ 1,557.56
999	Contingency	L.S.	1	\$ 170,980.00	\$ 170,980.00
	SUB - TOTAL				\$ 257,799.06
	ENHANCEMENT ITEMS				
721-75-1	Furnish And Install Gretchen Bench (including concrete base slab)	EA	2	\$ 2,652.33	\$ 5,304.66
721-74-1	Furnish And Install Scarborough Trash Receptacle (including concrete base slab)	EA	2	\$ 1,552.33	\$ 3,104.66
750	Furnish and install Bus Shelter, Complete (includes Gretchen bench, Scarborough trash receptacle, Timberform bollard)	EA	2	\$ 56,789.74	\$ 113,579.48
	TOTAL ENHANCEMENT ITEMS				\$ 121,988.80
	PROJECT GRAND TOTAL				\$2,216,099.72