



Saga Bay Park
Single Basketball Court
Three (3) Written Quotes

Vendor

Quote

Superior Park Systems, Inc.

\$47,325.00

Recreation Products & Services, Inc.

\$49,575.00

Diversified Business Associates, Inc.

\$49,871.00



SUPERIOR PARK SYSTEMS, INC.

"A CERTIFIED LOCAL MBE/SBE OWNED BUSINESS #22214"

"For All of Your Parks and Recreational Needs"

May 23, 2017

Quote No. 052317

Send To:

Town of Cutler Bay
Parks & Recreation Department
10720 Caribbean Blvd. Suite #510
Cutler Bay, FL 33189
Attention: Etienne Bejarano, Director

Re: "Saga Bay Park" Basketball Court Quote No. 052317

Superior Park Systems, Inc. quotes the following Regulation Basketball Court to High School Specifications Including All Site Prep:

'Saga Bay Park' Basketball Court 60'x100'

We will perform the following Scope of work:

1. Grubb grass, haul off site ☐
2. Cut and fill to prepare the sub grade, compact to 98% density ☐
3. No import or export of fills. ☐
4. Provide and place 6" nominal thickness of lime rock, laser graded and ☐ compacted to 98% density. ☐
5. Tack the rock base with AEP-225 liquid tack coat. ☐
6. Pave with 1" (one inch) of VIRGIN Type S-3 Hot Mix Asphalt ☐
7. We will furnish and install a fixed height 10' basketball pole, 4" OD gooseneck ☐ steel pole with a 4' overhang, a fan shaped aluminum backboards and heavy duty breakaway rims with a nylon nets. Two for the single court, and four for the double court. ☐
8. We will flood the new asphalt with water to check for low areas. We will let the courts dry IN THE SUN for one (1) hour. Then any areas holding water deeper than 1/8" will be patched ☐
9. We will Apply a four coat acrylic textured surface system. This will include two (2) coats of Laykold Acrylic resurfacer a n even textured wearing surface, and two (2) coats of Laykold Color Coat Concentrate a textured in depth colored finished playing surface. The Owner may choose the color from our standard color chart.

10. Hand mask and hand paint the 2" white textured playing lines for High School layout.

11. Clean up all of our construction debris and leave the courts ready for play

Total Cost

\$47,325

Comments: Project to commence 2-3 week after receipt of purchase order. Owner shall provide a storage area for paint drums and pallets of sand at both locations adjacent to the courts. Owner shall provide a source of potable water to within 100' of the courts at both locations. Owner shall provide an access road from the nearest paved surface to the court work area. The Contractor will not be responsible for damage to anything within the designated access roadway. And the Owner shall restore the access roadway to pre construction condition once the Contractor completes all work. Contingent on city approved soil bearing test.

Submitted by,



Mitchell Leitner, President

Recreation Products & Services, Inc.

1160 NW 101 AVENUE
PLANTATION, FL. 33322
OFFICE 954-270-2110

MIKEROZOS@BELLSOUTH.NET

QUOTATION #2418

MAY 24, 2017

TOWN OF CUTLER BAY
PARKS & RECREATION DEPT.
10720 CARRIBEAN BOULEVARD
CUTLER BAY, FL. 33189

SAGA BAY PARK BASKETBALL COURT CONSTRUCTION	AMOUNT
CONSTRUCT 1 HIGH SCHOOL REGULATION BASKETBALL COURT AS FOLLOWS: REMOVE TURF & PREPARE SUB GRADE FOR 98% COMPATION INSTALL 6" NOMINAL THICKNESS OF LIME ROCK COMPACTED TO 98% DENSITY COAT THE ROCK BASE WITH AEP LIQUID TACK COAT PAVE 1" TYPE S-3 HOT MIX ASPHALT INSTALL FOUR (4) 10' 4" OD STEEL BASKETBALL POSTS WITH 4' EXTENTION INSTALL FOUR (4) ALUMINUM FAN SHAPED BASKETBALL BACKBOARDS INSTALL FOUR (4) BREAKAWAY BASKETBALL RIMS WITH NYLON NET APPLY 2 COATS OF LAYKOLD ACRYLIC SURFACER APPLY 2 COATS OF LAYKOLD ACRYLIC COLOR COAT PAINT PLAYING LINES PER HIGH SCHOOL SPECIFICATIONS TOWN TO PROVIDE VEHICLE & EQUIPMENT ACCESS TO SITE TOWN TO PROVIDE POTABLE WATER WITHIN 100' OF SITE CLEAN UP SITE & REMOVE CONSTRUCTION MATERIALS & DEBRIS PROJECT TO COMMENCE 3-4 WEEKS AFTER RECEIPT OF PURCHASE ORDER QUOTE BASED ON SUB SOIL SURVEY BY OTHER SUITABLE FOR CONSTRUCTION	
TOTAL	\$49,575.00

Diversified Business Associates, Inc.

1419 Coolidge Street
Hollywood, Fl. 33020
Phone 305.968.6032
email: kiddmill56@gmail.com

QUOTE

QUOTE #287
DATE: JUNE 5, 2017

TO:

Town of Cutler Bay
P&R Dept.
Attn: Etienne Bejarano, Director
10720 Caribbean Blvd. Ste. #510
Cutler Bay, Fl. 33189

RE:

SAGA BAY PARK
BASKETBALL COURT

QUANTITY	DESCRIPTION	UNIT PRICE	TOTAL
1 BASKETBALL COURTS	<p>QUOTE IS FOR (1) ONE NEW 60' X 100' BASKETBALL COURT TO BE INSTALLED INCLUDING POLES, RIMS, NETS, BACKBOARDS, ETC AS FOLLOWS:</p> <p>PREPARE THE SITE TO 98% COMPACTION WITH LIME ROCK INCLUDING GRADING AND HAUL DEBRIS INSTALL 1' LAYER OF VIRGIN TYPE S-3 ASPHALT TO NO GREATER THAN 1/8" WATER HOLDING CAPACITY PROVIDE AND INSTALL ALL REQUIREMENTS FOR STANDARD BASKETBALL COURT S, TO INCLUDE: (2) TWO POLES (4" OD) TO CODE, FAN ALUMINUM BACKBOARDS, HEAVYDUTY BREAKAWAY RIMS, HARDWARE AND NETS FINAL SURFACE TO BE OF (2) TWO COATS LAYKOLD ACRYLIC AND (2) TWO COATS OF COLOR CONCENTRATE; OWNERS CHOICE OF STOCK COLORS</p> <p>*COMMENCEMENT 4-6 WEEKS AFTER PO IS RECEIVED. *NATIVE SOIL BEARING TEST TO BE APPROVED PRIOR TO INSTALLATION *OWNER SHALL PROVIDE A WATER SOURCE AND AN ACCEPTABLE ACCESS ROAD.</p> <p><u>KEITH B. MILLER</u> PRESIDENT</p>		
		TOTAL DUE	\$49,871.00