



**Lakes by the Bay Park**  
**Double Basketball Court**  
**Three (3) Written Quotes**

**Vendor**

**Quote**

**Superior Park Systems, Inc.**


**\$87,200.00**

**Diversified Business Associates, Inc.**

**\$95,895.00**

**Recreation Products & Services, Inc.**

**\$93,235.00**



# SUPERIOR PARK SYSTEMS, INC.

“A CERTIFIED LOCAL MBE/SBE OWNED BUSINESS #22214”

“For All of Your Parks and Recreational Needs”

May 11, 2017

---

## Quote No. 0511417

---

### Send To:

Town of Cutler Bay  
Parks & Recreation Department  
10720 Caribbean Blvd. Suite #510  
Cutler Bay, FL 33189  
Attention: Etienne Bejarano, Director

Re: “Lakes By The Bay Park” Basketball Court Quote No. 0511417

Superior Park Systems, Inc. quotes the following (2) Regulation Basketball Courts to High School Specifications Including All Site Prep:

### ‘Lakes By The Bay Park’ (2) Basketball Courts 120’x100’

We will perform the following Scope of work:

1. Grubb grass, haul off site
2. Cut and fill to prepare the sub grade, compact to 98% density
3. No import or export of fills.
4. Provide and place 6” nominal thickness of lime rock, laser graded and compacted to 98% density.
5. Tack the rock base with AEP-225 liquid tack coat.
6. Pave with 1” (one inch) of VIRGIN Type S-3 Hot Mix Asphalt
- 7.
8. We will flood the new asphalt with water to check for low areas. We will let the courts dry in the sun for one (1) hour. Then any areas holding water deeper than 1/8” will be patched
9. We will Apply a four coat acrylic textured surface system. This will include two (2) coats of Laykold Acrylic resurfacer a n even textured wearing surface, and two (2) coats of Laykold Color Coat Concentrate a textured in depth colored finished playing surface. The Owner may choose the color from our standard color chart.

10. Hand mask and hand paint the 2" white textured playing lines for High School layout.
11. Clean up all of our construction debris and leave the courts ready for play

**Total Cost**

**\$87,200.00**

**Comments:** Project to commence 2-3 week after receipt of purchase order. Owner shall provide a storage area for paint drums and pallets of sand at both locations adjacent to the courts. Owner shall provide a source of potable water to within 100' of the courts at both locations. Owner shall provide an access road from the nearest paved surface to the court work area. The Contractor will not be responsible for damage to anything within the designated access roadway. And the Owner shall restore the access roadway to pre construction condition once the Contractor completes all work.

Submitted by,



Mitchell Leitner, President

File: "Town of Cutler Bay" – Lakes by The Bay Park Basketball Courts quote 05/11/17

**Mobile (954) 445-7000   Office (954) 920-3352   Fax (954) 921-9563**  
**1418 Scott St. Hollywood, FL 33020   E-Mail – [mitch@superiorparksystems.com](mailto:mitch@superiorparksystems.com)**

**Diversified Business Associates, Inc.**

1419 Coolidge Street  
Hollywood, Fl. 33020  
Phone 305.968.6032  
email: kiddmill56@gmail.com

**QUOTE**

QUOTE #285  
DATE: MAY 17, 2017

**TO:**

Town of Cutler Bay  
P&R Dept.  
Attn: Etienne Bejarano, Director  
10720 Caribbean Blvd. Ste. #510  
Cutler Bay, Fl. 33189

**RE:**

LAKES BY THE BAY PARK  
BASKETBALL COURT

| QUANTITY                  | DESCRIPTION  | UNIT PRICE | TOTAL       |
|---------------------------|--|------------|-------------|
| 2<br>BASKETBALL<br>COURTS | <p><b>QUOTE IS FOR (2) TWO NEW REGULATION BASKETBALL COURTS TO BE INSTALLED INCLUDING POLES, RIMS, NETS, BACKBOARDS, ETC AS FOLLOWS:</b></p> <p>PREPARE THE SITE TO 98% COMPACTION WITH LIME ROCK INCLUDING GRADING AND HAUL DEBRIS<br/>INSTALL 1' LAYER OF VIRGIN TYPE S-3 ASPHALT TO NO GREATER THAN 1/8" WATER HOLDING CAPACITY<br/>PROVIDE AND INSTALL ALL REQUIREMENTS FOR STANDARD BASKETBALL COURT S, TO INCLUDE: (4) FOUR OF POLES (4" OD) TO CODE, FAN ALUMINUM BACKBOARDS, HEAVYDUTY BREAKAWAY RIMS, HARDWARE AND NETS<br/>FINAL SURFACE TO BE OF (2) TWO COATS LAYKOLD ACRYLIC AND (2) TWO COATS OF COLOR CONCENTRATE; OWNERS CHOICE OF STOCK COLORS</p> <p>*COMMENCEMENT 4-6 WEEKS AFTER PO IS RECEIVED.<br/>*NATIVE SOIL BEARING TEST TO BE APPROVED PRIOR TO INSTALLATION<br/>*OWNER SHALL PROVIDE A WATER SOURCE AND AN ACCEPTABLE ACCESS ROAD.</p> <p><u>KEITH B. MILLER</u><br/>PRESIDENT</p> |            |             |
|                           |  | TOTAL DUE  | \$95,895.00 |



# Recreation Products & Services, Inc.

1160 NW 101 AVENUE

PLANTATION, FL. 33322

OFFICE 954-270-2110

[MIKEROZOS@BELLSOUTH.NET](mailto:MIKEROZOS@BELLSOUTH.NET)

## QUOTATION #2399

**MAY 4, 2017**

### TOWN OF CUTLER BAY

PARKS & RECREATION DEPT.

10720 CARRIBEAN BOULEVARD

CUTLER BAY, FL. 33189

| LAKES BY THE BAY PARK BASKETBALL COURT CONSTRUCTION  | AMOUNT             |
|--|--------------------|
| CONSTRUCT 2 HIGH SCHOOL REGULATION BASKETBALL COURTS AS FOLLOWS:<br>REMOVE TURF & PREPARE SUB GRADE FOR 98% COMPATION<br>INSTALL 6" NOMINAL THICKNESS OF LIME ROCK COMPACTED TO 98% DENSITY<br>COAT THE ROCK BASE WITH AEP LIQUID TACK COAT<br>PAVE 1" TYPE S-3 HOT MIX ASPHALT<br>INSTALL FOUR (4) 10' 4" OD STEEL BASKETBALL POSTS WITH 4' EXTENTION<br>INSTALL FOUR (4) ALUMINUM FAN SHAPED BASKETBALL BACKBOARDS<br>INSTALL FOUR (4) BREAKAWAY BASKETBALL RIMS WITH NYLON NET<br>APPLY 2 COATS OF LAYKOLD ACRYLIC SURFACER<br>APPLY 2 COATS OF LAYKOLD ACRYLIC COLOR COAT<br>PAINT PLAYING LINES PER HIGH SCHOOL SPECIFICATIONS<br>TOWN TO PROVIDE VEHICLE & EQUIPMENT ACCESS TO SITE<br>TOWN TO PROVIDE POTABLE WATER WITHIN 100' OF SITE<br>CLEAN UP SITE & REMOVE CONSTRUCTION MATERIALS & DEBRIS<br>PROJECT TO COMMENCE 3-4 WEEKS AFTER RECEIPT OF PURCHASE ORDER<br>QUOTE BASED ON SUB SOIL SURVEY BY OTHER SUITABLE FOR CONSTRUCTION |                    |
| <b>TOTAL</b>   | <b>\$93,235.00</b> |