



Attachment "B"

Saga Bay Park Single Basketball Court Three (3) Written Quotes

<u>Vendor</u>	<u>Quote</u>
Superior Park Systems, Inc.	\$47,325.00
Recreation Products & Services, Inc.	\$49,575.00
Diversified Business Associates, Inc.	\$49,871.00



SUPERIOR PARK SYSTEMS, INC.

"A CERTIFIED LOCAL MBE/SBE OWNED BUSINESS #22214"

"For All of Your Parks and Recreational Needs"

August 17, 2017

Quote No. 0817817

Send To:

Town of Cutler Bay
Parks & Recreation Department
10720 Caribbean Blvd. Suite #510
Cutler Bay, FL 33189
Attention: Etienne Bejarano, Director

Re: "Saga Bay Park" Basketball Court Quote No. 0817817

Superior Park Systems, Inc. quotes the following Regulation Basketball Court to High School Specifications Including All Site Prep:

'Saga Bay Park' Basketball Court 60'x100'

We will perform the following Scope of work:

1. Grubb grass, haul off site ☐
2. Cut and fill to prepare the sub grade, compact to 98% density ☐
3. No import or export of fills. ☐
4. Provide and place 6" nominal thickness of lime rock, laser graded and ☐ compacted to 98% density. ☐
5. Tack the rock base with AEP-225 liquid tack coat. ☐
6. Pave with 1" (one inch) of VIRGIN Type S-3 Hot Mix Asphalt ☐
7. We will furnish and install a fixed height 10' basketball pole, 4" OD gooseneck ☐ steel pole with a 4' overhang, a fan shaped aluminum backboards and heavy duty breakaway rims with a nylon nets. Two for the single court, and four for the double court. ☐
8. We will flood the new asphalt with water to check for low areas. We will let the courts dry IN THE SUN for one (1) hour. Then any areas holding water deeper than 1/8" will be patched ☐
9. We will Apply a four coat acrylic textured surface system. This will include two (2) coats of Laykold Acrylic resurfacer a n even textured wearing surface, and two (2) coats of Laykold Color Coat Concentrate a textured in depth colored finished playing surface. The Owner may choose the color from our standard color chart.

10. Hand mask and hand paint the 2" playing lines (choice of colors) for High School layout.
11. Clean up all of our construction debris and leave the courts ready for play

Total Cost	<u>\$47,325</u>
-------------------	------------------------

Comments: Project to commence 2-3 week after receipt of purchase order. Owner shall provide a storage area for paint drums and pallets of sand at both locations adjacent to the courts. Owner shall provide an access road from the nearest paved surface to the court work area. The Contractor will not be responsible for damage to anything within the designated access roadway. And the Owner shall restore the access roadway to pre construction condition once the Contractor completes all work. Contingent on city approved soil bearing test.

Submitted by,



Mitchell Leitner, President

File: "Town of Cutler Bay" – Saga Bay Park Basketball Court quote 08/17/17

Mobile (954) 445-7000 Office (954) 920-3352 Fax (954) 921-9563
1418 Scott St. Hollywood, FL 33020 E-Mail – mitch@superiorparksystems.com

Recreation Products & Services, Inc.

1160 NW 101 AVENUE
 PLANTATION, FL. 33322
 OFFICE 954-270-2110

MIKEROZOS@BELLSOUTH.NET

QUOTATION #2399**AUGUST 17, 2017**

TOWN OF CUTLER BAY
 PARKS & RECREATION DEPT.
 10720 CARRIBEAN BOULEVARD
 CUTLER BAY, FL. 33189

SAGA BAY PARK 100'X60' BASKETBALL COURT CONSTRUCTION	AMOUNT
REMOVE TURF & PREPARE SUB GRADE FOR 98% COMPATION INSTALL LINE TACK ROCK BASE AEP -225 INSTALL 6" NOMINAL THICKNESS OF LIME ROCK COMPACTED TO 98% DENSITY COAT THE ROCK BASE WITH AEP LIQUID TACK COAT PAVE 1" TYPE S-3 HOT MIX ASPHALT INSTALL TWO (2) 10' 4" OD STEEL BASKETBALL POSTS WITH 4' EXTENTION INSTALL TWO (2) ALUMINUM FAN SHAPED BASKETBALL BACKBOARDS INSTALL TWO (2) BREAKAWAY BASKETBALL RIMS WITH NYLON NET APPLY 2 COATS OF LAYKOLD ACRYLIC SURFACER APPLY 2 COATS OF LAYKOLD ACRYLIC COLOR COAT PAINT PLAYING LINES PER H.S. SPECIFICATIONS SEVERAL COLORS AVAILABLE TOWN TO PROVIDE VEHICLE & EQUIPMENT ACCESS TO SITE TOWN TO PROVIDE POTABLE WATER WITHIN 100' OF SITE CLEAN UP SITE & REMOVE CONSTRUCTION MATERIALS & DEBRIS PROJECT TO COMMENCE 3-4 WEEKS AFTER RECEIPT OF PURCHASE ORDER QUOTE BASED ON SUB SOIL SURVEY BY OTHER SUITABLE FOR CONSTRUCTION CITY TO PROVIDE WATER TO SITE	
TOTAL	\$49,575.00

Diversified Business Associates, Inc.

1419 Coolidge Street
Hollywood, FL 33020
Phone 305.968.6032
email: kiddmill56@gmail.com

QUOTE

QUOTE #287
DATE: AUGUST 21, 2017

TO:

Town of Cutler Bay
P&R Dept.
Attn: Etienne Bejarano, Director
10720 Caribbean Blvd. Ste. #510
Cutler Bay, FL 33189

RE:

SAGA BAY PARK
BASKETBALL COURT

QUANTITY	DESCRIPTION	UNIT PRICE	TOTAL
1 BASKETBALL COURT	<p>QUOTE IS FOR (1) ONE NEW 60' X 100' BASKETBALL COURT TO BE INSTALLED INCLUDING POLES, RIMS, NETS, BACKBOARDS, ETC AS FOLLOWS:</p> <p>PREPARE THE SITE TO 98% COMPACTION WITH LIME ROCK INCLUDING GRADING AND HAUL DEBRIS INSTALL 1' LAYER OF VIRGIN TYPE S-3 ASPHALT TO NO GREATER THAN 1/8" WATER HOLDING CAPACITY PROVIDE AND INSTALL ALL REQUIREMENTS FOR STANDARD BASKETBALL COURT , TO INCLUDE: (2) TWO POLES, 10' FINISHED HEIGHT, 4" OD, TO CODE, FAN ALUMINUM BACKBOARDS, HEAVYDUTY BREAKAWAY RIMS, HARDWARE AND NETS TO HIGH SCHOOL SPECIFICATIONS ROCK CAP BASE/AEP 225 LIQUID TAC COAT FINAL SURFACE TO BE OF (2) TWO COATS LAYKOLD ACRYLIC AND (2) TWO COATS OF COLOR CONCENTRATE; OWNERS CHOICE OF STOCK COLORS</p> <p>*COMMENCEMENT 4-6 WEEKS AFTER PO IS RECEIVED. *NATIVE SOIL BEARING TEST TO BE APPROVED PRIOR TO INSTALLATION *OWNER SHALL PROVIDE A WATER SOURCE AND AN ACCEPTABLE ACCESS ROAD.</p> <p><u>KEITH B. MILLER</u> PRESIDENT</p>		
		TOTAL DUE	\$49,871.00